

Negotiated rate Comparative Statement

Name of Work : Providing RCC drain and impts to footpath at 1st A cross, Sharadamba nagara in ward no 16

Tender Notification No. RRND/EE/Ten/01/2014-15, Date: 04.06.2014

E-procurement No: BBMP/2013-14/OW/WORK_INDENT10733/CALL-4

Sl No.	Item Description	Unit	Quantity	As per Estimate Rate (PWD SR 2013-14 B'lore Circle.	Amount in Rs.	Rates quoted by		Negotiated Rates quoted by	
						RAGHAVENDRA B		RAGHAVENDRA B	
						Eate in Rs	Amount in Rs	Rate in Rs	Amount in Rs
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches	cum	335.28	227.88	76403.61	246.11	82515.76	239.00	80131.92
2	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading and	cum	435.86	76.85	33495.84	83.00	36176.38	81.00	35304.66
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size	cum	43.56	4290.84	186908.99	4634.11	201861.83	4504.00	196194.24
4	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface	sqm	633.60	271.08	171756.29	292.76	185492.74	285.00	180576.00
5	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready	cum	93.06	6468.12	601923.25	6985.56	650076.21	6789.00	631784.34
6	Providing T.M.T steel reinforcement for Bars Fe 415 R.C.C work including straightening, cutting, bending, hooking,	qtl	56.63	7380.72	417970.17	7971.17	451407.36	7747.00	438712.61
7	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and	nos	537.72	316.44	170156.12	341.75	183765.81	332.00	178523.04
8	Covering Slab(As per Data Rate approved 100mm thick)	sqm	237.60	1400.00	332640.00	1512.00	359251.20	1469.00	349034.40
9	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including	sqm	92.40	23.76	2195.42	65.32	6035.57	25.00	2310.00